

October 26, 2022

To: All Bidders

From: Kate Bailey
Director of Procurement

Re: ADDENDUM NO. 1
22-122.1 – Pier 78-80 Emergency Paving

This Addendum No.1 is issued to:

1. Set the period of performance for this project at thirty (30) calendar days starting with Notice to Proceed.
2. Provide a revised Project Description. Revised description below:

Project Description

Pavement base repair is required at the Pier 78-80 Terminal for large potholes that have developed and deteriorated in a high traffic area where machinery routinely fuels up and trucks queue, largely along rail tracks. See attached marked up arial photo.

- Red marked areas:
 - o 2” 12.5 mm wearing course mill and overlay track sections.
 - o Mix designs used should be 3 to < 10 million ESALS, WMA, and PG 64-22
- Green marked areas:
 - o 14” full depth repair; consisting of geofabric at subgrade, followed by 6” 2A subbase, 4” 25 mm base course, 2” 19mm binder course, 2” 12.5 mm wearing course.
 - o Mix designs used should be 3 to < 10 million ESALS, WMA, and PG 64-22
- Blue marked area (45’x 20’) in section F:
 - o 14” full depth repair; consisting of geofabric at subgrade, followed by 6” 2A subbase, 8” 3,500psi concrete pad.
 - o Since this is an active terminal, the concrete pad will need to be staged to allow the terminal forklifts to fill up while the concrete sets.

Bidders will provide PhilaPort with a lump sum bid price to perform the necessary repairs.

3. Provide a revised photo of the repair areas. Measurements on photo have been revised. (attached)
4. Clarify that the successful bidder must work closely with PhilaPort staff on logistics and operations of the terminal as it relates to the project.
5. Provide a copy of the Mandatory Site Meeting Sign in Sheet. (attached)

All other terms and conditions remain unchanged.

Bidders shall acknowledge receipt of this addendum by immediately emailing a copy of the completed acknowledgment to Kate Bailey at procurement@philaport.com

ACKNOWLEDGMENT OF RECEIPT OF ADDENDUM NO. 1

Project #22-122.1

Pier 78-80 Emergency Paving

Date _____

By _____

Company _____

Telephone _____

Fax _____

Email _____




Philadelphia Regional Port Authority
3460 North Delaware Ave. 2nd Floor
Philadelphia, PA 19134

REVISED

PHOTO OF REPAIR AREAS



- A - 110' x 10'
- B - 15' X 25'
- C - 25' X 15'
- D - 300' X 12'
- E - 24' X 15'
- F - 70' X 25'



Google





Philadelphia Regional Port Authority
3460 North Delaware Ave. 2nd Floor
Philadelphia, PA 19134

MANDATORY SITE MEETING
SIGN IN SHEET

MANDATORY SITE MEETING

Project #22-122.1 - Pier 78-80 Emergency Paving
 Wednesday October 26, 2022, at 11:00 A.M.

PRINTED NAME	COMPANY	PHONE	EMAIL	Diversity Certification (if applicable)
Tom Kenny	Harris Ribblehaus	610-476-6740	TKenny@HKGroup.com	
Bob Dierdorff	AP Const. Inc.	215-688-0533	bobd@apconstruction.com	
Jack Eller	JRC Group Inc	856-297-3423	Estimating@jrcgroupinc.com	
Crista Sessler	Franc Inc	6106370551	Crista@beni70ecomcst.net	✓
Bryan Fleming	Daves D Anderson	215-331-7150	Bryan@EJJAConstruction.com	
ERIC LANTO	James J Anderson	215-331-7150	EricL@jjaconstruction.com	
Jeff Weise	Seravalli	2159696500	jeffrey.weise@seravalli.com	
Phila Port:				
Kate Barber				
Mike Day				
Jim Hooper				
Tom Hooper				
Ben Willk				